

I:\2017\2017-211-GWSSOMIDLAND\001-MIDLAND4MILERD27THST-H-DWGS\CIVIL\PS-SHEETSET\SMIDLAND-ADMIN.DWG Plotted: 10/28/2020 2:42 PM By: Ashley Cline

CONTRACT ITEM NO.	CONTRACT ITEM	UNIT	ROADWAY		RETAINING WALLS		WATERLINE		PROJECT TOTALS	
			PLAN	AS CONST	PLAN	AS CONST	PLAN	AS CONST	PLAN	AS CONST
603-50042	42 INCH PLASTIC PIPE	LF	879						879	
603-50048	48 INCH PLASTIC PIPE	LF	774						774	
604-00305	INLET TYPE C (5 FOOT)	EACH	4						4	
604-00310	INLET TYPE C (10 FOOT)	EACH	2						2	
604-00505	INLET TYPE D (5 FOOT)	EACH	2						2	
604-00506	INLET TYPE D (SPECIAL) (5 FOOT)	EACH	1						1	
604-00510	INLET TYPE D (10 FOOT)	EACH	2						2	
604-19210	INLET TYPE R L 10 (10 FOOT)	EACH	1						1	
604-25006	VANE GRATE INLET SPECIAL (5 FOOT)	EACH	27						27	
604-25011	VANE GRATE INLET SPECIAL (10 FOOT)	EACH	2						2	
604-30005	MANHOLE SLAB BASE (5 FOOT)	EACH	5						5	
604-30010	MANHOLE SLAB BASE (10 FOOT)	EACH	11						11	(R-3)
604-30015	MANHOLE SLAB BASE (15 FOOT)	EACH	2						2	
604-30020	MANHOLE SLAB BASE (20 FOOT)	EACH	1						1	
604-39015	MANHOLE SPECIAL (15 FOOT)	EACH	1						1	
604-83108	8 INCH PLASTIC PIPE SEWER (POLYVINYL CHLORIDE)	LF	58						58	
606-00301	GUARDRAIL TYPE 3 (6-3 POST SPACING)	LF	3551						3551	
606-01390	END ANCHORAGE TYPE 3K	EACH	4						4	
606-02003	END ANCHORAGE (NONFLARED)	EACH	4						4	
606-10300	BRIDGE RAIL TYPE 3	LF	25		165				190	(R-3)
607-11450	FENCE SPLIT CEDAR	LF	152						152	
607-11455	FENCE WOOD	LF	1264						1264	
607-11500	FENCE STOCKADE	LF	158						158	
607-11525	FENCE (PLASTIC)	LF	75						75	(R-1)
607-11530	FENCE (SPECIAL)	LF	136						136	
607-53160	FENCE CHAIN LINK (60 INCH)	LF	53						53	
607-55040	MESH ANCHOR	EACH			200				200	
607-55100	WIRE MESH (DRAPED)	SF			28245				28245	
607-55103	CABLE NET (SPECIAL)	SF			64050				64050	
607-60120	20 FOOT GATE	EACH	1						1	
608-00000	CONCRETE SIDEWALK	SY	3699						3699	
608-00005	CONCRETE SIDEWALK (SPECIAL)	SY	1531						1531	
608-00010	CONCRETE CURB RAMP	SY	251						251	
608-00015	DETECTABLE WARNINGS	SF	309						309	
609-20010	CURB TYPE 2 (SECTION B)	LF	162						162	
609-20011	CURB TYPE 2 (SPECIAL)	LF	524						524	
609-21011	CURB AND GUTTER TYPE 2 (SECTION I-M)	LF	298						298	
609-21020	CURB AND GUTTER TYPE 2 (SECTION II-B)	LF	13012						13012	
609-21021	CURB AND GUTTER TYPE 2 (SECTION II-M)	LF	435						435	
609-24004	GUTTER TYPE 2 (4 FOOT)	LF	378						378	
610-00020	MEDIAN COVER MATERIAL (PATTERNED CONCRETE)	SF	3016						3016	
613-01202	2 INCH ELECTRICAL CONDUIT (PLASTIC) (INSTALL ONLY)	LF	7820						7820	
613-01302	3 INCH ELECTRICAL CONDUIT (PLASTIC) (INSTALL ONLY)	LF	1423						1423	
613-01602	6 INCH ELECTRICAL CONDUIT (PLASTIC)(INSTALL ONLY)	LF	1384						1384	
613-07199	PULL BOX (INSTALL ONLY)	EACH	5						5	
613-08000	VAULT (INSTALL ONLY)	EACH	9						9	
613-30300	LIGHT STANDARD ALUMINUM (30 FOOT)	EACH	21						21	
613-40010	LIGHT STANDARD FOUNDATION	EACH	21						21	
613-50155	SECONDARY SERVICE PEDESTAL (INSTALL ONLY)	EACH	1						1	
614-00011	SIGN PANEL (CLASS I)	SF	72						72	(R-2)
614-01503	STEEL SIGN SUPPORT (2-INCH ROUND)(POST AND SOCKET)	EACH	32						32	
614-80003	RECTANGULAR RAPID FLASHING BEACON	EACH	1						1	
615-65000	PRECAST IRRIGATION STRUCTURE	EACH	2						2	(R-1)
619-00002	WATER SERVICE	EACH					14		14	
619-00007	CONNECT TO EXISTING WATERLINE	EACH					12		12	
619-51290	18 INCH PLASTIC PIPE	LF					6778		6778	(R-1)

Computer File Information	
Print Date:	10/28/20
Last Modification Date:	10/22/20
Drawing File Name:	SMidland-Admin
Autocad Ver. 2018	Scale: As Shown Units: English
SGM Project No.:	2017-211.001 Quality Control: RGN

Sheet Revisions			
Rev.	Date	Comments	Init.
1	10.21.20	Revised Items/Quantities	AMC
2	10.22.20	Revised Items/Quantities	MDF
3	10.28.20	Updated Quantities	AMC

118 West Sixth Street, Suite 200
Glenwood Springs, CO 81601
970.945.1004 www.sgm-inc.com

As Constructed	
No Revisions:	-
Revised:	-
Void:	-

South Midland Ave. Improvements Summary of Approximate Quantities (3)			
Engineer:	MDF	Structure	---
Drawn By:	AMC	Numbers	---
Sheet Subset:	SAQ	Subset Sheets:	3 of 4

Project No./Code	
No.:	BUILD M535-006
Code:	22933
Sheet Number:	15